

9-16

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-155-21,185 0000

NE NE NE, SECTION 22 TOWNSHIP 23 RANGE 8W

OPERATOR LICENSE # 30606 4950 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR MURFIN DRILLING CO INC
NAME & 250 N WATER STE 300
ADDRESS WICHITA KS 67202

LEASE NAME: FOSTER 22-1

COUNTY: RENO 123.50
WELL TOTAL DEPTH: 3800' (3745')

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 264'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KELSO CASING PULLING INC
ADDRESS: P O BOX 347 CHASE KS 67524-0347 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 13:00 DAY: 16 MONTH: 9 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: STAN FROETCHNER
COMPANY NAME: MURFIN DRILLING CO INC PHONE: 913-483-5371

WERE: SAND TO 3590' & CAP W/5 SX CMT - SHOOT PIPE OFF & SPOT
35 SX CMT @ 1250' - 35 SX CMT @ 800' - CIRC CMT FROM
310' TO SURF - PERFS @ 3640'-3648' - 5-1/2" @ 3785'

PLUGGING PROPOSAL RECEIVED BY: PHIL WORLEY

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 16:00 DAY: 16 MONTH: 9 YEAR: 1993

ACTUAL PLUGGING REPORT:
SANDED TO 3590' & TOPPED W/5 SX CMT - SHOT PIPE OFF @
2820' - PULLED PIPE TO 1250' & SPTD 35 SX CMT - PULLED
PIPE TO 750' & SPTD 35 SX CMT - PULLED PIPE TO 340' &
CIRC 80 SX CMT TO SURF. RECOVERED 2820' 5-1/2"

REMARKS: USED 60/40 POZ W/4% GEL BY ALLIED #5456

I DID OBSERVE THIS PLUGGING.

MS
Michael R. Wilson (AGENT)

INVOICED
DATE 10-1-93
INV. NO. 38808

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 20 1993
REV. 3/89
CONSERVATION DIVISION
WICHITA, KS