

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
4-15-68  
APR 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Burton of Pickrell Drlg. Co. has this  
date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Ks.

Lease Name: Miller "O" Well No. 1

Location: SE SW SW Sec. 2 Twp. 19 Rge. 20 (E)(W) X

County Rush Total Depth 4350 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 550' and displace  
70 sc cement thru drill pipe. Heavy mud to 280' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Geo F. Massey  
Conservation Division Agent