

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAYGovernor
Chairman
Commissioner
Commissioner

Carol J. Larson, Executive Secretary

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Morgenstern of Clarke Corp. has this
date requested permission to plug the following described well:Mr. Morgenstern guarantees payment of the plugging fee.Operator's full Name: Clarke Corp.Complete Address: 107 W. Fowler, Medicine Lodge, Ks. 67104Lease Name: Skelly Well No. 1Location: C E/2 SE SE Sec. 30 Twp. 32s Rge. 12 (E)(W) WCounty: Barber Total Depth 4690 Oil Well XGas Well Input Well SWD Well D & A Lost Hole STATE CORPORATION COMMISSIONMr. Morgenstern was instructed to plug the well as follows AUG 20 1980240' 8 5/8" casing. 4 1/2" casing set at 4689'-CIBP set at CONSERVATION DIVISION4300'-Pref., at 4430'-Casing split at 4007' to 4047'-Squeeze Wichita, Kansasw/425 sax cement. Hole in pipe at 1852', squeeze w/325 saxcement. Pull 1080' casing-Bridge at 240'-Dump 5 yard groutin 8 5/8" casing to top of casing. Medicine Lodge Ready Mix.

Very truly yours,

Conservation Division Agent