

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1967

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed March 1, 1967.

Dear Sir:

Mr. Norman Thompson of Garvey Drilling Company has this
date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name: Kirkbride Well No. # 1

Location: C NE NW Sec. 28 Twp. 32 Rge. 12 (E)(W)W

County Barber Total Depth 4470' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

317' of 8 5/8" surface pipe, cement circulated with 235 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent