

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed November 14, 1967.

Dear Sir:

Mr. Wayne Dobbs of E. K. Edmiston Drilling has this  
date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston & Amerada

Complete Address: 425 First National Bank Bldg., Wichita, Kansas 67202

Lease Name: Bundren Well No. # 1

Location: C SW NE Sec 28 Twp. 33 Rge. 15 (E)(W) W

County Barber Total Depth 3320' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

1001' of 8 5/8" surface pipe, cemented with 600 sacks. Fill  
hole with drilling mud to 350', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent

