

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 31 1962
 10-31-62
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. L. C. Brau. of E. K. Edmiston Drig. Co Inc. has this
 date requested permission to plug the following described well:

Mr. L. C. Brau guarantees payment of the plugging fee.

Box 323 Larned, Kns.
 Operator's full Name: E. K. Edmiston Drlg. Co. Inc.

Complete Address: 501 First National Bank Bldg. Wichita, Kansas.

Lease Name: Groendyke # 1 Well No. #1

Location: C-W $\frac{1}{2}$ Sec. 13 Twp. 33S Rge. 12 (E) (W) X

County Barber Total Depth 4500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. L. C. Brau. was instructed to plug the well as follows:

355' of 8 5/8" surface pipe circulated with 250 sacks cement.

Hole filled to 200' with heavy drill mud, $\frac{1}{4}$ sack hulls,

1st cementing plug and 20 sacks cement through drill pipe.

Hole filled to 40' with heavy drill mud, $\frac{1}{4}$ sack hulls, 2nd

cementing plug and 10 sacks cement to base of cellar. Rat
hole bridged, 2sacks cement. Mouse hole bridged and 2 sacks
cement.

Herman Justus
 Conservation Division Agent