



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

JEWEL M. OGDEN, Director

*CP2*

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 27 1962  
8-27-62  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date August 20 1962, 1961, authorized the following plugging operation:

Operator's full Name: Santa Fe Pipe & Supply.

Complete Address: Box 562 Great Bend, Kansas.

Lease Name: Robbins Gallup Well No. #1

Location: NE SW SW Sec. 18 Twp. 31 Rge. 15 (E) (W)

County: Barber Total Depth: 4801'

Oil Well  Gas Well  Input Well  SWD Well

D & A  Other well as hereafter indicated:

Abandoned Oil Well

Operator was instructed to plug well as follows:

~~4 1/2" pipe set at 4799'. Plugged back to 4745'. Perforated between 4707' and 4727'. Sanded to 4700' & 5 Sacks cement. 285 ft. 8 5/8" surface pipe circulated with cement. Hole filled with mud to 250' and 10" rock bridge, 20 sacks cement. Hole filled with mud to 40', 10' rock bridge and 10 sacks cement to bottom of cellar~~

Very truly yours,

*Herman Justus*

