

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECORDED
STATE CORPORATION COMMISSION
JAN 3 1966
1-3-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jack Insminger of German Drilling Company has this date requested permission to plug the following described well:

Mr. Insminger guarantees payment of the plugging fee.

Operator's full Name: Shenandoah Oil Corporation

Complete Address: 406 Mutual Savings Bldg., Fort Worth, Texas

Lease Name: Ray Rusk Well No. # 1

Location: C of Section Sec. 19 Twp. 31 Rge. 15 (E)(W) W

County Barber Total Depth 4900' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Insminger was instructed to plug the well as follows:

350' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent