

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15-007-20030-00-00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1967

CONSERVATION DIVISION  
Wichita, Kansas

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
Filed June 15, 1967.

Dear Sir:

Mr. Norman Thompson of Garvey Drilling Company has this  
date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: T. A. Mace

Complete Address: 5101 N. Pennsylvania, Oklahoma City, Okla.

Lease Name: Walker Well No. # 1

Location: App. C SW Sec. 6 Twp. 31 Rge. 15 (E)(W) W

County Barber Total Depth 4680' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

938' of 8 5/8" surface pipe, cemented with 500 sacks. Fill hole  
with drilling mud to 500', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat & mouse holes with 4 sack

Very truly yours,

Arline Elving

Conservation Division Agent