

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 8 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Dale Buchheister of John O. Farmer Inc. has this

date requested permission to plug the following described well:

Mr. Buchheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer Inc.

Complete Address: 370 W. Wichita, Russell, Kansas

Lease Name: Kitner Well No. # 1

Location: C 31 SW/4 Sec. 6 Twp. 31 Rge. 15 (E) (W) W

County Barber Total Depth 1200 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Buchheister was instructed to plug the well as follows:

297' of 8 5/8" surface pipe, cement circulated with 275
sacks. Circulation was lost at 1200', hole was abandoned,
and rig skidded 17' to the east. Set solid rock bridge
225', cement with 20 sacks. Fill hole with mud to 40',
10' rock bridge, cement with 10 sacks to base cellar.
Rat hole bridged and cemented with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent