

15-007-20002-00-00

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1967
1-23-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill, filed
January 4, 1967

Dear Sir:

Mr. Norman Thompson of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name: Thomas "G" Well No. # 1

Location: App. C NE NW Sec. 32 Twp. 32 Rge. 12 (E)(W) W

County Barber Total Depth 4581' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

296' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill hole with drilling mud to 260', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Aulie Elving
Conservation Division Agent