



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 24 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed January 5, 1968.

Dear Sir:

Mr. R. E. Domstead of Texaco, Inc. has this  
date requested permission to plug the following described well:

Mr. Domstead guarantees payment of the plugging fee.

Operator's full Name: Texaco, Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas 67202

Lease Name: Hazel Smith Well No. # 1

Location: C NW SW SW Sec. 35 Twp. 32 Rge. 12 (E)(W) W

County Barber Total Depth 4825' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Domstead was instructed to plug the well as follows:

292' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill  
hole with drilling mud to 275', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent