

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 24 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Co. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Co.

Complete Address: 416 Union Center Bldg., Wichita, Kansas

Lease Name: Noble Well No. # 1

Location: C NW SW Sec. 31 Twp. 32 Rge. 12 (E) (W) W

County Barber Total Depth 4625 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

281' of 8 5/8" surface pipe, cement circulated with 175
sacks. Fill hole with mud to 275', 1st cementing plug, 1/2 sack hulls,
cement with 25 sacks. Fill hole with mud to 40', 2nd cementing
plug, 1/2 sack hulls, cement with 15 sacks. Bridge and cement
rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent