

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSASVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1964

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. H. C. Hickman of Stickle Drilling Co. has this
date requested permission to plug the following described well:Mr. Hickman guarantees payment of the plugging fee.Operator's full Name: Sunray DX Oil Co.Complete Address: 321 West Douglas, Wichita, KansasLease Name: Roy Platt Well No. # 2Location: 100' E/C NW NW NW Sec. 17 Twp. 33 Rge. 15 (E) (W) WCounty Barber Total Depth 5060 Oil WellGas Well Input Well SWD Well D & A X Lost Hole Mr. Hickman was instructed to plug the well as follows:

231' of 13 3/8" surface pipe, cemented with 225 sacks. Fill
Hole with drilling mud to 225', 1st cementing plug, bridge
with hulls, and cement with 40 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 20 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent