

State of Kansas



WM. H. AVERY Governor
WILLIAM I. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
JAN 17 1967
1-17-67
CONSERVATION DIVISION
Wichita, Kansas
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dunham of Aspen Drilling Co. has this
date requested permission to plug the following described well:

Mr. Dunham guarantees payment of the plugging fee.

Operator's full Name: Aspen Drilling Company

Complete Address: P. O. Box 783 Great Bend, Kansas

Lease Name: Dyer Well No. 1

Location: SW NE SW Sec. 21 Twp. 19 Rge. 16 (E)(W) X

County Rush Total Depth 3840' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunham was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 450' and displace

25 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with

2 sc cement.

Very truly yours,

Leo F. Massey
Conservation Division Agent