

State of Kansas



JOHN ANDERSON, Jr. Governor  
 WILLIAM L. MITCHELL, Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 24 1964

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Jim Shipley of Graybol Oil Corporation has this  
 date requested permission to plug the following described well:

Mr. Shipley guarantees payment of the plugging fee.

Operator's full Name: Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa, Tulsa, Oklahoma

Lease Name: Hull Well No. # 1

Location: C NE NE Sec. 14 Twp. 31 Rge. 15 (E) (W) W

County Barber Total Depth 4800 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Shipley was instructed to plug the well as follows:

809' of 8 5/8" surface pipe, cement circulated with 460 sacks.  
Fill hole with drilling mud to 300', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving