

KANSAS

4 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

SEP 18 1972
9-18-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil Co.

Complete Address Box 400 Duncan, OK

Lease Name Sanders Well No. 1

Location C SE/NE Sec. 16 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4767

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1182 Great Bend, KS License No. 623

Operation Completed: Hour 1:00 PM Day 14 Month 9 Year 1972

The above well was plugged as follows:

171 ft 8 5/8 surface pipe cemented with 160 sacks. 4510 ft 5 1/2 long
string cemented with 100 sacks. Top perf. 4353 ft. Sand to 4340 ft,
5 sacks cement with bailer. Pulled 3030 ft 5 1/2. Set 10 ft rock
bridge at 240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *J. Russell Bickerton*
Well Plugging Supervisor

INVOICED

DATE 9/18/72

INV. NO. 6339-W