

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1965
11-3-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beardmore Drilling Company

Complete Address: 700 One Twenty Bldg., Wichita, Kansas

Lease Name Liebst Well No. # 1

Location C NE SE Sec. 14 Twp. 31 Rge. 11 (E) (W)W

County Barber Total Depth 4884'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Burch Exploration

Address: 1011 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour 12:30PM Day 1st Month Nov. Year 1965

The Above well was plugged as follows:

261' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 250', 1st cementing plug, bridged solid
with drv cement and hulls on fluid at 250', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with 2
sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED
DATE 11/3/65
INV. NO. 2103-W