

15-095-00357-00-01

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mack Oil Co.

Complete Address: 812 Union Center, Wichita, Kansas

Lease Name Rollmann Well No. # 1

Location C NW NE Sec. 35 Twp. 27 Rge. 6 (E) (W) W

County Kingman Total Depth 3995

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 4:00PM Day 24th Month Oct. Year 1963

The Above well was plugged as follows:

254' of 8 5/8" surface pipe, cement circulated, 3955' of 2 7/8" tubing
was run for long string, cemented with 175 sacks, pozmix. Top perforation
3795'. Tubing was shot off at 3348', 10 sacks of cement was pumped into
tubing at 3348'. Fluid level in hole was 270', plug and 10' rock bridge,
was set at 270', cemented with 25 sacks. Hole was filled with mud to
40', 10' rock bridge, cemented with 10 sacks to base cellar.
3348' of 2 7/8" tubing was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 10/28/63
INV. NO. 4954-W

Signed: Audie Elving
Well Plugging Supervisor