

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Ralph Rusk Well No. # 1

Location C SW SW Sec. 32 Twp. 31 Rge. 15 (E) (W) W

County Barber Total Depth 4945'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Pickrell Drilling Company

Address: 705 Fourth National Bank Bldg., Wichita, Ks. License No. _____

Operation Completed: Hour 6:30PM Day 28th Month July Year 1966

The Above well was plugged as follows:

. 246' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid to 240', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED
DATE 8/3/66
INV. NO. 3690-11