

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 8 1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Dunne-Gardner Drilling Company, Inc.

Complete Address: 300 Schweiter Bldg., Wichita, Kansas

Lease Name Rusk Well No. # 1

Location C SE NE Sec. 30 Twp. 31 Rge. 15 (E) (W) W

County Barber Total Depth 4280'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Dunne-Gardner Drilling Company, Inc.

Address: 300 Schweiter Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 6:30PM Day 2nd Month Jan. Year 1965

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cemented with 225 sacks. Hole was filled  
with drilling mud to 260', 1st cementing plug, bridged solid with hulls  
on fluid at 260', and cemented with 25 sacks. Hole was filled with  
drilling mud to 40', 2nd cementing plug, bridged solid with hulls on  
fluid at 40', and cemented with 10 sacks to the base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 1-8-65

INV. NO. 498-W

Signed: Archie Elving  
Well Plugging Supervisor