

KANSAS

Form CP-3  
Rev. 6-9-67

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 10 1967

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202Intent to Drill,  
filed June 15, 1967.Operator's Full Name T. A. MaceComplete Address 5101 N. Pennsylvania, Oklahoma City, OklahomaLease Name Walker Well No. # 1Location App. C SW Sec. 6 Twp. 31 Rge. 15 (E) (W) WCounty Barber Total Depth 4680'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated Plugging Contractor Garvey Drilling CompanyAddress R. R. # 2, Great Bend, Kansas 67530 License No. Operation Completed: Hour 5:30 A.M. Day 7th Month July Year 1967

The above well was plugged as follows:

938' of 8 5/8" surface pipe, cemented with 500 sacks. Hole was filled  
with drilling mud to 500', 1st cementing plug, bridged with 1 sack of  
dry cement and 1/2 sack of hulls on fluid at 500', and cemented with 24  
sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,  
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40',  
and cemented with 9 sacks to the base of the cellar. Rat and mouse holes  
bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging SupervisorDATE 7-10-67INV. NO. 5545-W