

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 8 1963

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name John O. Farmer Inc.

Complete Address: 370 W. Wichita, Russell, Kansas

Lease Name Kitner Well No. # 1

Location C SL SW/4 Sec. 6 Twp. 31 Rge. 15 (E) (W) W

County Barber Total Depth 1200

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Lost Hole

Plugging Contractor: John O. Farmer Inc.

Address: 370 W. Wichita, Russell, Kansas License No.

Operation Completed: Hour 9:00AM Day 5th Month May Year 1963

The Above well was plugged as follows:

297' of 8 5/8" surface pipe, cement circulated with 275 sacks.Circulation was lost at 1200', hole was abandoned and rig was skidded17' east. A solid rock bridge was set at 225', cemented with 1 sack andlet set. Globe Cementing Co. pumped 25 sacks cement on this plug, openended. Cement was left to harden, hole was filled with drilling mud to40', rock bridge, cemented with 10 sacks to base cellar. Rat hole wasbridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE

5/8/63

INV. NO.

9032-4

Signed:

Arthur Elving  
Well Plugging Supervisor