

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1966

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name Gayle E. Toland & CompanyComplete Address: P. O. Box 94336, Oklahoma City, OklahomaLease Name Ketner Well No. # 1Location S/2 SW Sec. 6 Twp. 31 Rge. 15 (E) (W) WCounty Barber Total Depth 4791'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Flint Engineering & Construction CompanyAddress: Box 950, El Dorado, Kansas License No. 547Operation Completed: Hour 5:30PM Day 1st Month Dec. Year 1966

The Above well was plugged as follows:

900' of 8 5/8" surface pipe, cemented with 500 sacks. 4700' of 4 1/2"
long string, no record on cement. Top perferation 4587'. Bottom of
the hole was sanded to 4550', and cemented with 3 sacks, through the
dump bailer. 3200' of 4 1/2" long string was recovered from the hole.
Fluid level in the hole was at 600', bridge plug and rock bridge from
600' to 590', and cemented with 25 sacks. Hole was filled with mud to
40', rock bridge from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 12/6/66INV. NO. 4396-W