

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill, filed
January 4, 1967

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name Thomas "G" Well No. # 1

Location App. C NE NW Sec. 32 Twp. 32 Rge. 12 (E) (W) W

County Barber Total Depth 4581'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No.

Operation Completed: Hour 12:45AM Day 20th Month Jan. Year 1967

The Above well was plugged as follows:

296' of 8 5/8" surface pipe, cement circulated with 250 sacks. Hole
was filled with drilling mud to 260', 1st cementing plug, bridged with
1 sack of dry cement and 1/2 sack of hulls on fluid at 260', and cemented
with 24 sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40',
and cemented with 9 sacks to the base of the cellar. Rat and mouse holes
bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aubie Elving
Well Plugging Supervisor

DATE 1/23/67
INV. NO. 4641-U