

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasIntent to Drill,
Filed January 5, 1968.RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1968
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Texaco, Inc.Complete Address: 614 Bitting Bldg., Wichita, Kansas 67202Lease Name Hazel Smith Well No. # 1Location C NW SW SW Sec. 35 Twp. 32 Rge. 12 (E) (W)WCounty Barber Total Depth 4825'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: K & E Drilling, Inc.Address: 719 Union Center Bldg., Wichita, Ks. 67202 License No. Operation Completed: Hour 7:30AM Day 23rd Month January Year 1968

The Above well was plugged as follows:

292' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole was
filled with drilling mud to 275', 1st cementing plug, bridged with 2 sacks
of dry cement and 1/2 sack of hulls on fluid at 275', and cemented with 23
sacks, with cement from 265' to 190'. Hole was filled with drilling mud
to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack
of hulls on fluid at 40', and cemented with 9 sacks to the base of the
cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

1/24/68

INV. NO.

7/43-4

Signed:

Archie Elving
Well Plugging Supervisor