

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 - 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Hershberger Exploration Inc.

Complete Address Suite 230 Garvey East 200 W. Douglas Wichita, Ks

Lease Name Randels Well No. 1

Location C SE/NW Sec. 34 Twp. 32 Rge. 12 (E) (W)W

County Barber Total Depth 4832

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Oilfield Service

Address 107 W Fowler Medicine Lodge, Ks License No. 583

Operation Completed: Hour 10:00 AM Day 5 Month 5 Year 1972

The above well was plugged as follows:

250 ft 8 5/8 surface pipe cements circulated. 4831 ft 4 1/2 long string
cemented with 100 sacks. Top perf. 4769 ft. Sand back to 4740 ft,
3 sacks cement with bailer. Pulled 4277 ft 4 1/2. Set 10 ft rock
bridge at 240 ft. Fill hole with 4 yds redmix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: A. Russell Bihunter
Well Plugging Supervisor

INVOICED

DATE 5/8/72
INV. NO. 5689-W