

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name General American Oil Co., of Texas

Complete Address: P. O. Box 1358, Seminole, Oklahoma

Lease Name Stodder Estate Well No. # 1

Location SW SW SW Sec. 17 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4975'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 4:00PM Day 21st Month Feb. Year 1966

The Above well was plugged as follows:

333' of 10 3/4" surface pipe, cemented with 250 sacks. 4541' of 7" long
string, cemented with 200 sacks. Plug back T.D. 4410'. Top perferation
4390'. 50 sacks of cement was pumped on bottom to a top of 4100'. 3000'
of 7" long string was recovered from the hole. Hole was filled with mud
to 315', rock bridge from 315' to 305', and cemented with 30 sacks.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 15 sacks to the base of the cellar.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

FEB 24 1966

2-24-66

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/24/66

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 2998-W