

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-30595-00-00  
Spot: SENWSENE Sec/Twnshp/Rge: 17-31S-15E  
3318 feet from S Section Line, 899 feet from E Section Line  
Lease Name: BLAKE Well #: 1  
County: MONTGOMERY Total Vertical Depth: 1431 feet

Operator License No.: 34779  
Op Name: LR ENERGY, INC.  
Address: 8150 N. CENTRAL EXPY, STE 1605  
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1076		150 SX
SURF	8.625	20		4 SX
T1	2.375	1107		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/15/2013 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: JACOB MCCLAIN Company: \_\_\_\_\_ Phone: (620) 627-2499

Proposed Plugging Method: Spot 50' cement plug. Gel spacer to 1097. Pump 220' cement plug over perforations. Pump gel spacer to 250' to surface. Pump 250' cement plug to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/15/2013 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 1238' gelled hole and spotted 25 sack plug to cover all perforations. Pulled up to 250' and circulated cement to surface. Pulled 2" and topped well off. A total of 55 sacks of 60/40 pozmix cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1096	1097		
1058	1062		
1039	1041		
1003	1009		
985	989		
904	907		
878	879		

RECEIVED  
OCT 01 2013  
KCC Chanute Dist. #3

DS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] (TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 03 2013

CONSERVATION DIVISION  
WICHITA, KS