

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-30977-00-00  
Spot: SWNENWNW Sec/Twnshp/Rge: 16-31S-15E  
4704 feet from S Section Line, 4613 feet from E Section Line  
Lease Name: BLAKE Well #: 4-16  
County: MONTGOMERY Total Vertical Depth: 1482 feet

Operator License No.: 34779  
Op Name: LR ENERGY, INC.  
Address: 8150 N. CENTRAL EXPY, STE 1605  
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1477		150 SX
SURF	8.65	21		4 SX
T1	2.375	1228		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/15/2013 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: JACOB MCCLAIN Company: \_\_\_\_\_ Phone: (620) 627-2499

Proposed Plugging Method: Spot 50' cement plug on bottom. Gel spacer to 1170'. Pump 300' cement plug to cover perforations. Pump gel spacer to 250' to surface. Pump 250' cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/15/2013 2:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 1466' gelled hole and spotted 10 sack plug. Pulled up to 1170' and spotted 20 sack plug. Pulled up to 250' and circulated cement to surface. Pulled 2" and topped well off. A total of 55 sacks of 60/40 pozmix cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1169	1170		
1168	1170		
1101	1105		
1062	1064		
1061	1064		
1041	1044		
1005	1011		
987	991		
986	990		
879	880		
878	880		
102	1106		

RECEIVED  
OCT 01 2013  
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

DS

District: 03

Signed

*Duane A Sims*  
10/24/13  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 03 2013

CONSERVATION DIVISION  
WICHITA, KS