

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-30691-00-01  
Spot: NWSESESE Sec/Twnshp/Rge: 16-32S-16E  
335 feet from S Section Line, 338 feet from E Section Line  
Lease Name: LINN Well #: 16-16  
County: MONTGOMERY Total Vertical Depth: 1265 feet

Operator License No.: 34779  
Op Name: LR ENERGY, INC.  
Address: 8150 N. CENTRAL EXPY, STE 1605  
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1130		
PROD	4.5	1252		130 SX
SURF	8.625	20		4 SX
T1	2.375	1099		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/15/2013 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Revd. from: JACOB MCCLAIN Company: \_\_\_\_\_ Phone: (620) 627-2499

Proposed Plugging Method: Spot 50' cement plug on bottom. Gel spacer to 1138'. Pump 450' cement plug over perforations. Pump gel spacer to 250' to surface. Pump 250' cement to surface.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 03/15/2013 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Ran 2-3/8" cement string to td. Pumped 10 sacks. Pulled to 1128' and pumped 30 sacks. Gel pumped. Pulled to 250' and circulated cement to surface. Pulled remaining cement string and topped off, 65 sacks of 60/40 poz mix cement reported used.

Perfs:

Top	Bot	Thru	Comments
1136	1138		
1082	1083		
1081	1082		
817	818		
816	818		
782	784		
756	757		
755	756		
730	735		
703	706		
702	706		

RECEIVED

SEP 26 2013

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine  
(TECHNICIAN)

KCC WICHITA

Form CP-2/3

SEP 30 2013

RECEIVED