

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-21958-00-01  
Spot: SESENWNW Sec/Twnshp/Rge: 34-33S-35W  
3983 feet from S Section Line, 4003 feet from E Section Line  
Lease Name: SKINNER T Well #: 34-2  
County: STEVENS Total Vertical Depth: 2900 feet

Operator License No.: 32730  
Op Name: FOUR STAR OIL & GAS COMPANY  
Address: 1400 SMITH ST- RM 47046  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1161		
CIBP		2614		
PROD	4.5	2899	0	WITH 550 SX CMT
SURF	8.625	621		WITH 350 SX CMT

Well Type: SWD UIC Docket No: D27584.0 Date/Time to Plug: 09/18/2013 8:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: KEITH PAINTER Company: Phone: (580) 467-0258

Proposed Plugging Method: Tbg set CIBP @ 1165' w/ 75 sks Class "C" cement 1164' to surface

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/18/2013 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 1161'. PUMP 75 SX CMT FROM 1130' TO 0' WITH 75 SX CMT. TOO H W/TBG.  
TOP OFF 4 1/2" WITH 20 SX CMT. PUMP 45 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2660	2804		
1215	1363		

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

OCT 22 2013

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed

*Ken Jehlik*  
10/24/13 (TECHNICIAN)  
\* cc to UIC 10/22/13

RECEIVED

OCT -7 2013

KCC DODGE CITY

Form CP-2/3

*ADW*