

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-00364-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 4-34S-40W
2475 feet from N Section Line, 2475 feet from E Section Line
Lease Name: VANSANT MATTIE Well #: 1
County: MORTON Total Vertical Depth: 2594 feet

Operator License No.: 32730
Op Name: FOUR STAR OIL & GAS COMPANY
Address: 1400 SMITH ST- RM 47046
HOUSTON, TX 77002

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 2363 | | WITH 20 SX CMT |
| PROD 7 | | 2599 | 0 | WITH 400 SX CMT |
| SURF | 10.75 | 470 | | WITH 275 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/24/2013 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Tbg set CIBP @ 2363' w/ 20 sks Class "C" cement , circulate hole w/ mud. 50 sks cement @ 1750'. 100 sks Class "C" cement 570' to surface. CHECK BACKSIDE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 09/24/2013 12:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 2363' WITH 20 SX CMT. 1ST PLUG AT 1768' WITH 50 SX CMT. 2ND PLUG AT 570' WITH 105 SX CMT. CMT CIRCULATED TO SURFACE. CHECK BACKSIDE WITH 10 SX CMT AT 300#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2556 | 2574 | | |
| 2436 | | | |
| 2413 | | | |

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 07 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed _____

Kenny Sullivan
10/24/13
(TECHNICIAN)

RECEIVED

SEP 26 2013

KCC DODGE CITY