

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23918-00-00  
Spot: N2N2S2 Sec/Twnshp/Rge: 36-9S-25W  
2310 feet from S Section Line, 2640 feet from W Section Line  
Lease Name: MCGRATH UNIT Well #: 36-1  
County: GRAHAM Total Vertical Depth: 4098 feet

Operator License No.: 8914  
Op Name: H & C OIL OPERATING INC.  
Address: PO BOX 86  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3948		
PROD	5.5	4098		180 SX
SURF	8.625	324		250 SX
T1	2.375	3886		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/07/2013 10:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: BOB PLANTE Company: H & C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: PC at 2173' w/150 sx QMDC  
Perforations: 3825' - 3868'  
CIBP at 3890'  
Ordered 300 sx 60/40 pozmix 4% gel cement and 12 sx gel

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/07/2013 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3860'. Quality Pumped 12 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2174' and pumped 200 sx cement. Cement circulated. PTOH. Topped 5 1/2" casing with 20 sx cement. Casing full. Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3964	3970		
3909	3912		
3866	3868		
3856	3859		

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 15 2013


CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY

Plugged through: TBG

District: 04

Signed

  
10/24/13 (TECHNICIAN)

CM

OCT 09 2013