

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23953-00-00
Spot: NENESESW Sec/Twnshp/Rge: 36-9S-24W
1150 feet from S Section Line, 2400 feet from W Section Line
Lease Name: GANO UNIT Well #: 1-36
County: GRAHAM Total Vertical Depth: 4100 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	295		225 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/02/2013 12:00 AM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: STEVE Company: H2 DRILLING LLC Phone: (620) 770-2214

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 10/02/2013 3:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st plug @2110 w/25 sx
2nd plug @985 w/100 sx
3rd plug @345 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED
Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 15 2013
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Richard Williams
10/24/13 (TECHNICIAN) CM

OCT 09 2013