

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22191-00-00
Spot: SWNENWSW Sec/Twnshp/Rge: 9-11S-16W
2234 feet from S Section Line, 4339 feet from E Section Line
Lease Name: CRAIG W Well #: 3
County: ELLIS Total Vertical Depth: 1017 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1010		300 SX
SURF	8.625	160		175 SX

Well Type: SWD UIC Docket No: D20281.0 Date/Time to Plug: 08/27/2013 9:00 AM
Plug Co. License No.: 34093 Plug Co. Name: SUMMIT WELL SERVICE LLC
Proposal Rcvd. from: ROLAND NYP Company: HERMAN L. LOEB LLC. Phone: (785) 737-3242

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement; 600 # hulls.
PBTD-1010'
Perforations- 590'-690' CH
Perforated 1010'. Cement to surface.
Milled on well and lost hole.
GPS: 39.10961 -099.10832
2232' FSL 4238' FEL SW NE NW SW

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2013 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Summit Well Service ran in hole with tubing to 591'. Basic rigged to tubing and mixed and pumped 55 sx cement w/50 # hulls mixed in to circulate cement to surface.
Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 5 sx cement to pressure with 270 psi and 260 psi shut in pressure.
Hooked up to 8 5/8" surface casing and pumped 5 sx cement to pressure with 250 psi and 250 psi shut in pressure.

Perfs:

Top	Bot	Thru	Comments
590	690		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: BASIC ENERGY SERVICES

Plugged through: TBG

SEP 09 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed [Signature] (TECHNICIAN)

AUG 29 2013

cc to MAC 8/10/13