

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22892-00-00  
Spot: SWNENWSW Sec/Twnshp/Rge: 21-31S-11W  
2148 feet from S Section Line, 981 feet from W Section Line  
Lease Name: ROBERTS Well #: 1  
County: BARBER Total Vertical Depth: 4997 feet

Operator License No.: 3372  
Op Name: DIXON ENERGY, INC.  
Address: 8100 E 22ND N BLDG 300, STE 200  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4780		WITH 2 SX CMT
PROD	5.5	4997	2300	WITH 150 SX CMT
SURF	8.625	336		WITH 235 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/09/2013 10:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: TJ DIXON Company: DIXON ENERGY Phone: (316) 264-9632

Proposed Plugging Method: SET CIBP @ 4780' & 2 SX CMT. PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/09/2013 12:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4780' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 345' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4830	4833		

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

OCT 15 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed Stephen J. Pfeifer  
10/14/13 (TECHNICIAN)

RECEIVED  
10/15  
OCT - 15 2013

KCC DODGE CITY

*[Handwritten signature]*