

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23975-00-00  
Spot: NENESWSE Sec/Twnshp/Rge: 12-6S-21W  
1110 feet from S Section Line, 1560 feet from E Section Line  
Lease Name: BROBST-MORRIS Well #: 1  
County: GRAHAM Total Vertical Depth: 3762 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		180 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2013 12:00 AM  
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC  
Proposal Rcvd. from: STEVE Company: H2 DRILLING LLC Phone: (620) 770-2214

Proposed Plugging Method: Ordered 220sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE  
Date/Time Plugging Completed: 10/14/2013 3:15 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st plug @1830 w/25 sx  
2nd plug @1090 w/100 sx  
3rd plug @315 w/40 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Remarks: ALLIED

Plugged through: DP

District: 04

Signed Ed Schumacher  
10/18/13 (TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

OCT 17 2013

OCT 23 2013  
CONSERVATION DIVISION  
WICHITA, KS