

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24153-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 5-6S-20W
965 feet from S Section Line, 2020 feet from E Section Line
Lease Name: BURKER TRUST Well #: 1
County: ROOKS Total Vertical Depth: 3680 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		185 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/23/2013 12:00 AM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: STEVE CRAIG Company: H2 DRILLING LLC Phone: (620) 770-2214

Proposed Plugging Method: Ordered 270 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: NONE
Date/Time Plugging Completed: 10/23/2013 10:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st plug @3620 w/50 sx
2nd plug @1780 w/25 sx
3rd plug @1050 w/100 sx
4th plug @325 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: CONSOLIDATED
Plugged through: DP

KCC WICHITA
NOV 07 2013
RECEIVED

District: 04

Signed Darrel Dipman
10/18/13 (TECHNICIAN) CM

OCT 28 2013