

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02765-00-00
Spot: NWNESEW Sec/Twnshp/Rge: 33-8S-24W
2312 feet from S Section Line, 2956 feet from E Section Line
Lease Name: BROWN D Well #: 3
County: GRAHAM Total Vertical Depth: 4023 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4023		150 SX
SURF	8.625	216		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2013 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: EXPRESS WELL SERVICE & SUPPL Phone: (620) 275-2963

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 7 sx gel and 500 # hulls. Perforations at 3922' - 3945'. Shot perforations at 2150' and 1350'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/11/2013 4:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3870' and pumped 7 sx gel followed by 75 sx cement and 150 # hulls. Pulled tubing to 2483' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1512' and pumped 170 sx cement. Good circulation of cement. Tied on to backside and squeezed w/50 sx cement. Shut in pressure 100 psi. Topped casing off w/25 sx cement.

GPS: 39.31215 -100.00619

Perfs:


Top	Bot	Thru	Comments
3922	3945		

Remarks: SWIFT CEMENT TICKET # 25717

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 15 2013

OCT 21 2013

CONSERVATION DIVISION
WICHITA, KS