

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-02769-00-00  
Spot: SWSE Sec/Twnshp/Rge: 33-8S-24W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: BROWN D Well #: 7  
County: GRAHAM Total Vertical Depth: 3950 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3950		175 SX
SURF	8.625	188		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/15/2013 12:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JOE SMITH Company: EXPRESS WELL SERVICE & SUPPL Phone: (620) 275-2963

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 500 # hulls and 7 sx gel. Perforation at 3908' - 3912'. Shot perforations at 2150' and 1350'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/15/2013 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3880' and pumped 7 sx gel followed by 75 sx cement w/150 # hulls. Pulled tubing to 2552' and pumped 125 sx cement w/150 # hulls. Pulled tubing to 1362' and pumped 150 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 25 sx cement. Tied on to backside and squeezed w/75 sx cement. Shut in pressure 100 psi.

GPS: 39.30754 -100.00300

Perfs:

Top	Bot	Thru	Comments
3908	3912		

Remarks: SWIFT CEMENT TICKET # 24646

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*(Signature)*  
10/16/13 (TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 23 2013

CONSERVATION DIVISION  
WICHITA, KS

OCT 16 2013