

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-02772-00-00  
Spot: NWSW Sec/Twnshp/Rge: 33-8S-24W  
1980 feet from S Section Line, 660 feet from W Section Line  
Lease Name: BROWN D Well #: 10  
County: GRAHAM Total Vertical Depth: 3992 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3992		150 SX
SURF	8.625	190		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/21/2013 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JOE SMITH Company: EXPRESS WELL SERVICE & SUPPL Phone: (620) 275-2963

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 7 sx gel and 500 # hulls. Perforations at 3929' to 3956'. Shot perforations at 2150' and 1350'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/21/2013 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3882' and pumped 7 sx gel followed by 75 sx cement w/150 # hulls. Pulled tubing to 2555' and pumped 125 sx cement w/150 # hulls. Pulled tubing to 1387' and pumped 115 sx cement. Good circulation of cement. Pulled tubing out. Topped off w/25 sx cement. Tied on to backside and squeezed w/50 sx cement. Shut in at 150 psi.

GPS: 39.31126 -100.01203

Perfs:


Top	Bot	Thru	Comments
3950	3956		
3929	3956		

Remarks: SWIFT CEMENT TICKET # 25123

Plugged through: TBG

District: 04

Signed

  
10/24/13 (TECHNICIAN)

CM

OCT 22 2013

KCC WICHITA

Form CP-2/3

OCT 24 2013

RECEIVED