

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-30159-00-00  
Spot: NESWNWNW Sec/Twnshp/Rge: 29-30S-18W  
662 feet from N Section Line, 655 feet from W Section Line  
Lease Name: COBB Well #: 1  
County: KIOWA Total Vertical Depth: 5120 feet

Operator License No.: 31142  
Op Name: PETROLEUM PROPERTY SERVICES, IN  
Address: 125 N MARKET SUITE 1251  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3200		WITH 2 SX CMT
CIBP		4925		
PROD	5.5	5119	0	WITH 75 SX CMT
SURF	8.625	707		WITH 350 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/11/2013 1:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: LEON KUHN Company: PETROLEUM PROPERTY SERVICE Phone: (785) 483-1551

Proposed Plugging Method: SET CIBP @ 3200' WITH 2 SX CMT. PERFORATE @ 1140' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/12/2013 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 3200' WITH 2 SX CMT. PERFORATED AT 1140'. PUMPED 300 SX CMT WITH GOOD RETURNS THROUGHOUT. CMT DID NOT CIRCULATE. 9/12/13: TOC 200' PERFORATED @ 175'. CIRCULATED CMT TO SURFACE WITH 100 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5021	5069		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED  
SEP 13 2013  
KCC DODGE CITY

Signed Eric MacLaren (TECHNICIAN)

KCC WICHITA Form CP-2/3

SEP 18 2013

RECEIVED