

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-059-22421-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 1-18S-20E
609 feet from S Section Line, 2039 feet from E Section Line
Lease Name: BRUNER.E Well #: 3
County: FRANKLIN Total Vertical Depth: 757 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	748		0 SX
SURF	7	20		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/25/2013 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL/FM, THEN PMP IN AND FILL PROD CSG W/CMT, PRESS UP ON SAME AND SHUT WELL IN. IF CAN NOT PMP FLUID, RIH W/1" TBG TO BTM, PMP AND FILL PROD CSG W/CMT, POOH 1" TBG, TOP OFF CSG W/CMT, PRESS UP ON SAME AND SHUT WELL IN. RETURN AT A LATER DATE AND CUT CSG OFF BELOW "PLOW LEVEL".

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 06/25/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO TD IN 2-7/8 INCH CASING AND FILL TO SURFACE WITH PORTLAND CEMENT. PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE SHUTTING IN AT 810 PSI. USE TOTAL OF 27 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
726	734		
543	566		

RECEIVED
NOV 06 2013
KCC Chanute Dist. #3
LS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] 11/6/13
(TECHNICIAN)

✓ 11/6/13

KCC WICHITA

Form CP-2/3

NOV 12 2013

RECEIVED