

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-30568-00-00
Spot: E2E2SESW Sec/Twnshp/Rge: 9-24S-18E
660 feet from S Section Line, 2700 feet from E Section Line
Lease Name: KIRK Well #: 14-9
County: ALLEN Total Vertical Depth: 1146 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	20		10 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/12/2012 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: Run tubing to TD. Spot cement at TD, 500', and 250' to surface.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE
Date/Time Plugging Completed: 12/12/2012 12:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 2.875" drill pipe to 1146'. Consolidated hooked onto drill pipe and circulated with fresh water. Mix and pumped gel down the 2.875" casing. Pumped 85 sacks cement from 1146' to 800'. Pull drill stem up to 550'. Pumped 12 sacks of cement through the 2.875" drill stem from 550' to 500'. Pulled drill stem up to 250'. Circulated cement from 250' to surface. Pulled the rest of the drill stem out of the hole. Topped well off with cement. A total of 160 sacks of portland cement was used to plug this well.

Perfs:

RECEIVED

OCT 30 2013

KCC Chanute Dist. #3

LD

Remarks:

Plugged through: DP

District: 03

Signed



(TECHNICIAN)

✓ 11/21/13

KCC WICHITA

NOV 01 2013

RECEIVED