

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-03240-00-00
Spot: SWSWNESW Sec/Twnshp/Rge: 9-24S-18E
1520 feet from S Section Line, 3760 feet from E Section Line
Lease Name: KIRK Well #: RB24
County: ALLEN Total Vertical Depth: 962 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	941		100 SX
SURF	7	5		0 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/10/2013 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: REX ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: COMPANY UNIT RIH W/1 1/4" TBG TO TD - CONSOLIDATED OIL WELL SERV GEL HOLE UP THEN PUMP 150' CMT PLUG @TD - SERVICE UNIT PULL TBG UP TO 500'. PUMP 50' CMT PLUG. PULL TBG TO 250' CMT TO SURFACE, POOH TBG TOP WELL OFF. COME BACK LATER & CUT SURFACE OFF "FLOW DEPTH".

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/10/2013 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing to TD. Circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled the 1" pipe and topped the well off with cement. A total of 29 sacks of cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
949	961		
RECEIVED OCT 30 2013 KCC Chanute Dist. #3 RD			

Remarks:

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)

KCC WICHITA

NOV 01 2013

RECEIVED