

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-19190-00-00
Spot: NWENWSE Sec/Twnshp/Rge: 9-24S-18E
2565 feet from S Section Line, 1770 feet from E Section Line
Lease Name: KIRK Well #: RB27
County: ALLEN Total Vertical Depth: 947 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	932		110 SX
SURF	7	8		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/10/2013 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: COMPANY UNIT RIH W/1 1/4" TBG TO TD. CONSOLIDATED GEL HOLE UP PUMP 150' CMT PLUG @TD. PUL TBG UP TO 500' PMP 50' CMT PLUG- PULL TBG UP TO 250' PUMP CMT TO SURFACE - POOH TBG TOP OFF WELL COME BACK LATER CUT SURFACE OFF PLOW DEPTH

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL
Date/Time Plugging Completed: 06/10/2013 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe to 875'. Washed 1" pipe down the inside of the 2" casing to 947'. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled the 1" pipe. Topped the well off with cement. A total of 29 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
937	947		

RECEIVED
OCT 30 2013
KCC Chanute Dist. #3
RD

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

✓ 11/24/13

KCC WICHITA

Form CP-2/3

NOV 01 2013

RECEIVED