

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-23405-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 9-24S-18E
1205 feet from S Section Line, 3830 feet from E Section Line
Lease Name: KIRK Well #: RB 38
County: ALLEN Total Vertical Depth: 950 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD | 2 | 927 | | 15 SX |
| SURF | 6.25 | 50 | | 10 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/07/2013 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: COMPANY UNIT RIH W/1" TO TD GEL HOLE UP . PUMP 50' CMT PLUG PULL 1" UP TO 500' PUMP 50' CMT PLUG PULL 1" UP TO 250' PUMP CEMENT TO SURFACE. PULL 1" OUT TOP WELL OFF. LATER GO BACK CUT SURFACE OFF TO PLOW DEPTH.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 05/16/2013 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" hydrill to 950'. Mixed and pumped gell down 1". Pumped cement down 1" at TD. Pulled 1" to 500'. Spotted cement at 500'. Pulled 1" to 250'. Circulated cement from 250' to surface. Pulled the rest of the 1". Topped well off with cement. A total of 42 sacks of portland cement was reported used to plug this well.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 927 | 950 | | |


RECEIVED
OCT 30 2013
KCC Chanute Dist. #3
RD

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)
✓ 11/21/13

KCC WICHITA

Form CP-2/3

NOV 01 2013

RECEIVED