

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-29782-00-00  
Spot: S2N2S2SE Sec/Twnshp/Rge: 31-32S-15E  
880 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: KROEKER-GOLEY Well #: 108  
County: MONTGOMERY Total Vertical Depth: 1183 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1169		137 SX
SURF		22		
SURF	6.625	41		4 SX

Well Type: EOR UIC Docket No: E22527.15 Date/Time to Plug: 09/12/2013 12:00 AM  
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC  
Proposal Rcvd. from: REX ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RIH W/1" TO TD GEL HOLE TO TOP CONSOLIDATED OIL WELL SERVICES PUMP 50' CEMENT PLUG PULL 1" TO 500' PUMP 50' CMT PLUG. PULL 1" TO 250' PUMP CMT TO SURFACE. SERVICE UNIT PULL 1" OUT OF HOLE HOOK TO 2 7/8" TBG PRESSURE UP SHUT WELL IN TOP OFF COME BACK AT LATER DATE CUT SURFACE OFF BELOW PLOW DEPTH.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 09/12/2013 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1168' and circulated cement to surface. Pulled 1" and topped well off. Hooked onto casing and squeezed well. Shut in with 300 psi on casing. A total of 30 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1130	1140		

RECEIVED  
OCT 24 2013  
KCC Chanute Dist. #3  
DS

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 03

Signed [Signature]  
(TECHNICIAN)

cc to WCC 11/06/13  
✓ 11/21/13

KCC WICHITA Form CP-2/3

OCT 28 2013

RECEIVED