

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-059-24361-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 36-17S-20E  
340 feet from S Section Line, 3706 feet from E Section Line  
Lease Name: R B ANDERSON Well #: 3(3A)  
County: FRANKLIN Total Vertical Depth: 760 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	754		75 SX
SURF	7.625	20		6 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2013 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL/FM, THEN PMP IN AND FILL PROD CSG W/CMT, PRESS UP ON SAME AND SHUT WELL IN. IF CAN NOT PMP FLUID, RIH W/1" TBG TO BTM, PMP AND FILL PROD CSG W/CMT, POOH 1" TBG, TOP OFF CSG W/CMT, PRESS UP ON SAME AND SHUT WELL IN. RETURN AT A LATER DATE AND CUT CSG OFF BELOW "PLOW LEVEL"

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE  
Date/Time Plugging Completed: 06/26/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO TD IN 2-7/8 INCH CASING AND FILL TO SURFACE WITH PORTLAND CEMENT. PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE SHUTTING IN AT 690 PSI. USE TOTAL OF 30 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
674	675		
626	635		

RECEIVED

OCT 30 2013

KCC Chanute Dist. #3

LS

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature] 10/30/13  
11/21/13

(TECHNICIAN)

KCC WICHITA

NOV 01 2013

RECEIVED